

#### **Public Information Center #1**

December 7 – 18, 2020









#### **Presentation Overview**

- Project Team
- Project Delivery Process
- Project Location / Limits
- Purpose and Need
- Existing Conditions
- Approved Project Plan
- Construction Staging
- Detour
- Project Schedule and Construction Cost Estimate
- Feedback









#### **Project Team**



Aaron T. Watson – Deputy Administrator/Director DOT&I

George A. Fallat, PE – County Engineer

Basit A. Muzaffar, PE (Sunny) – Project Manager, Assistant

County Engineer



**Kyle Skala** – Bureau of Local Aid and Economic Development



**John Coscia, Jr.** – Manager, Office of Project Implementation



**Bernard Boerchers, PE, PTOE** – Project Manager **William Farrow, PE** – Deputy Project Manager









## **Project Delivery Process**


Local Concept Development	Local Preliminary Engineering	Final Design / Right of Way Acquisition	Construction
Purpose and Need Statement	Approved Design Exception Report	Construction Contract	Completed Construction
Data Collection and	Cost Estimates (Final Design ROW	Document and PS&E Package	As-Builts
Environmental Screening Report	and Construction)	Environmental Reevaluations	Undata and Finaliza Design
Selection of Preliminary Preferred Alternative	Approved Environmental  Document	Environmental Permits	Update and Finalize Design Communications Report
		Acquisition of ROW	Close-Out Documentation
NEPA Classification	Approved Project Plan	Update Design	
Concept Development Report	Preliminary Engineering Report	Communications Report	
Create Design Communications Report	Update Design Communications Report		












#### **Purpose and Need**

- Purpose is to replace Structure No. 1100-055 (County No. 140.9)
- Rated 3-Serious due to condition of the superstructure
  - Deck rating: 4-Poor
  - Superstructure rating: 3-Serious
  - Substructure rating: 5-Fair
- Sufficiency Rating of 46.2













#### **Existing Conditions (Bridge)**

# **Structural Information and Deficiencies**

 Carries Lincoln Avenue over Amtrak NEC and Assunpink Creek

- Built in 1931
- Reconstructed in 1965
- Comprised of 8 simple spans
- Steel through-girders (fracture critical)
- Steel floorbeams and concrete deck
- Severely corroded steel
- Large areas spalled / delaminated concrete
- Substandard vertical underclearance











## **Existing Conditions (Roadway)**



# **Roadway Information and Deficiencies**

- 2 lane, urban minor arterial
- Not posted (25 mph)
- 18-foot wide lanes, no shoulders (CSDE)
- 6-foot wide sidewalk on either side
- Roadway/pedestrian lighting
- Broken back horizontal curves
- Substandard vertical stopping sight distance
- Substandard cross slope
- Clear zone (14-16') with obstructions









#### **Existing Conditions (Rail)**

#### **Railroad Operations**

- Amtrak Northeast Corridor (NEC)
  - Amtrak
  - NJ Transit
  - Freight
- 5 mainline and 1 siding electrified tracks
- Overhead catenary lines and feeder cables
- Inactive NJ Transit tracks and old platform






















## **Approved Project Plan**












#### **Construction Staging**



STAGE 1 - CONSTRUCTION










#### **Construction Staging**



STAGE 2 - CONSTRUCTION











#### **Project Schedule and Construction Cost Estimate**

Concept **Development Completed:** Spring 2018

**Preliminary Engineering Est. Completion** Winter 2020

**Final Design Est. Completion** Fall 2022

Construction Est. Spring 2023 - Fall 2025

**Estimated Construction Cost:** \$38 Million Dollars (in 2020 dollars) Estimated Right of Way Costs is \$1 Million Dollars









## **Public Feedback**

# Submit Questions, Comments and Suggestions at the link below:

## For more information contact:

Basit Muzaffar, PE, Assistant County Engineer

DOT&I Mercer County, Division of Engineering

640 South Broad Street

Trenton, NJ 08650-0068

Email: bmuzaffar@mercercounty.org

